

BEML LIMITED, BANGALORE COMPLEX

Ref:6300028710

Date: 25.07.2019

ISSUED TO:	Period of contract:	03 Months
	EMD :	Rs. 11,960/-

Sub:Minor civil works for repair and increasing the height of compound wall at various locations near Mallespalya bus stand , near GM Palya behind Kalamandira, BEML Medical center, near Ayyappa Temple road and LB shastri Nagar at BEML TOWNSHIP, BEML Limited, Bangalore complex, Bangalore-560075

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in figures & in words	Amount (Rs)
1	Dismantling the existing Size stone masonry wall built in cement mortar and disposal of unserviceable material from the premises etc complete., all as specified and as directed Engineer In-charge. Note: The dismantled materials/debris should be removed immediately from the premises without disturbing the public vehicle moments and the serviceable materials like size stones shall be stacked at a place shown for re-use and the quoted rate is deemed to include for all lead, lift etc.	Cu.M	25		
2	Providing & constructing size stone masonry in CM 1:6 for superstructure using good quality size stones,well bonded at every 1.5 Mtrs apart solidly hearted each course well levelled etc.,complete all as specified and as directed by Engineer in charge. Note: a) The rate quoted is deemed to include for dressing of the stones & corner stones.	Cu.M	90		
3	Providing and laying in position Plain Cement Concrete for coping in mix proportion 1:2:4 using 20mm down graded granite aggregates,mechanical/manual mixing, and placing at all levels, consolidating, curing and finishing including dewatering wherever necessary, including labour, lead, lift, tools, plant & machinery, hire & fuel charges & all other other incidental charges etc.,complete all as specified and as directed by Engineer in charge.	Cu.M	5		
4	Preparing the existing wall surfaces & providing Flush pointing in cement mortar 1:4 to block in course or squared rubble coursed/uncoursed masonry including curing, tools & tackles etc.,complete all as specified and as directed by Engineer in charge.	Sqm	200		
5	Constructing size stone masonry in CM 1:6 for superstructure using available size stones, well bonded at every 1.5 Mtrs apart solidly hearted, each course well levelled etc.,complete all as specified and as directed by Engineer in charge. Note: The rate quoted is deemed to include for dressing of the stones & corner stones.	Cu.M	10		
6	Carting away the unwanted and unusable excavated soil, debris, garbage outside the site premises to a distance to a distance exceeding 1.5km but not exceeding 5km including transportation, all lead and lift etc complete all as specified and directed by Engineer-in-charge.	Cu.M	30		

Sl. No	Description	Unit	Qty	Rate/unit in figures & in words	Amount (Rs)
	Note:				
	(1)The rate quoted for all the above items is deemed to include for providing and removal of scaffolding/staging as required for execution of the work under the relevant item				
	(2)Interested bidders/contractors are requested to visit the site and acquaint themselves with the site conditions before submission of their quote/offer for the work as the works have to be carried out at different locations of BEML Township				
	Total value of work excluding GST			Rs.	
	GST		%	Rs.	
	Total value of work inclusive of GST			Rs.	

Total Amount in words Rupees_____

Signature of the Contractor
with seal