

#### SCOPE OF WORK:-

Soil testing in our factory premises to check safe bearing capacity of soil for foundation of traverser of 100T capacity, for movement of coaches/wagons at 2 different locations in Rail Coach division II,,BEML KGF Complex.

#### Terms and conditions :

- 1.The firm should be approved by NABL.
- 2.Boring of three bore holes at each traverser locations are to be carried out.
- 3.The rate for each individual item to be quoted.
- 4.Total Mobilization and demobilization of men and auger equipments to be quoted.
5. The reports to be submitted within Six days after Completion of field work.
6. The work to be commenced within Six days from the date of receipt of Purchase Order.
7. The field investigations and the required laboratory tests shall be conducted as per the relevant Indian Standards.
8. All the site clearances will be made by BEML at free of cost.
9. L1 will be arrived based on cumulative prices of item 1 & 2.