

ISSUED TO:	Period of contract:	One Month
	EMD :	Rs. 5,520/-

Sub:Supply of M-Sand, filling in bags (25kgs each), stitching, stacking, loading and unloading for squeeze test of MRS-1 Metro Cars at BEML Limited, Bangalore Complex, Bangalore

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
1	Supplying of M-sand (Plastering Dry sand) and stacking at a place shown including all lead, lift, transportation, loading and unloading at the place shown inside factory etc., complete all as specified and directed by Engineer in charge Note:- The total quantity of M-sand required is 60MT (Dry weight) and Sample of M-sand (Plastering Dry sand) to be approved by BEML.	Tonne	60		
	GST on Item no(1)		%		
2	Supplying of durable good quality double layer HDPE empty Bags of 25kg capacity and stacking at specified location as directed by Engineer-in-charge. Note:Sample of HDPE bags to be approved by BEML.	Nos	2400		
	GST on Item no(2)		%		
3	Filling only the available dry M-sand in double layer HDPE bags including stitching the sand bags, weighing on a weighment scale (each bags weighing 25 Kgs) and stacking at specified location as directed by Engineer-in-charge. Note:- 1) Required quantity of M-Sand bags is 2400 numbers and each bag weighing 25 kg. 2) The rate is deemed to include for hiring a calibrated weighing scale for weighment and stitching machine for stitching the bags 3) The rate is deemed to include for cost of thread for stitching the HDPE bags after filling sand and labour cost for stitching. 4) The cost is deemed to include for labour for filling the M sand into HDPE bags. 5) The rate is deemed to include for cost of additional plastic sheet to cover the stacked M-sand bags at the stored location inside BEML factory to avoid ingress of moisture and loss of material due to rains when stored.	Nos	2400		
	Total value of work excluding GST			Rs.	
	TOTAL GST AMOUNT			Rs.	
	Total value of work inclusive of GST			Rs.	

Total Amount in words Rupees\_\_\_\_\_

Signature of the Contractor  
with seal