

The following blank Schedule 'A'- Bill of quantities to be filled with the rates by the tenderer and to be

ISSUED TO:	Period of	Three Months
	EMD :	Rs. 9800/-

Sub: Proposed Interlocking paving for walkway at existing Ambedkar Park at BEML Township, Bangalore Complex, Bangalore.

SCHEDULE 'A' - BILL OF QUANTITIES (CIVIL WORKS)

Sl. no	Description	Unit	Qty.	Rate/ unit in fig. & In words Rs.	Amount. Rs.
1	Surface excavation not exceeding 30cm in depth but exceeding 1.5m in width as well as 10sqm on plan including disposal of excavated earth upto 50m and lift upto 1.5m. Disposed soil to be levelled and neatly dressed etc as per direction of Engineer-in-charge.	Sq. M	300.0		
2	Providing and laying 75mm thick compacted bed of Manufactured sand below Interlock Pavers including spreading, watering, compacting, filling the joints with sand etc all complete as per direction of Engineer-in-charge.	Sq. M	250.0		
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade and made by block making machine with strong vibratory compaction (approved size, design, shape and colour) laid in required pattern etc as per direction of Engineer-in-charge.	Sq. M	250.0		
4	Providing and laying factory made PCC Kerb stone of size 75mmX300mmX600mm made of 1:3:6 Plain cement concrete laid in position to required line, level and curvature jointed with cement mortar 1:3 (1 Cement: 3 coarse sand) including making joints with or without grooves (thickness of joints except at sharp curve shall not more than 5mm) including making for drainage of water opening wherever required, etc complete etc as per direction of Engineer-in-charge.	RM	400.0		
	Total Amount (Rs.) excluding GST				
	GST Amount				
	Total Amount (Rs.) including GST				

Note: The rates quoted for all the above items is deemed to include for providing and removal of scaffolding/staging as required for the works.

(Total Amount in words Rupees.....
.....)

Sig. of Contractor.

