

BILL OF QUANTITIES

Sub-Proposed Interior Work in BEML RO, chennai

Sl. No.	Description of work	UOM	Qty	Rate (Rs.)	Amount (Rs.)
A)	INTERIOR WORKS				
1	Providing and fixing 3" thk. glazed ply partition made out of 19mm BWR grade plywood for the 2'X2' grid inside and finished with 8mm BWR ply with 1mm laminate covering the grid on either side with 8mm clear glass secured around with rubber wood beading etc., complete all as specified and directed	Sft	150		
2	Providing and fixing of 32mm laminated flush door including 3"X2" Padak hard wood frame,doorcloser, door stopper, handle and glass view panel etc., complete all as specified and directed	Nos	1		
3	Providing and fixing of vertical blinds (Parrytex or equivalent make) for the sliding aluminum windows	Sft	90		
4	Providing and fixing of frosted film stickering for the glass panels of wooden partition as per the approved design etc., complete all as specified and directed	Sft	35		
5	Providing Painting for the walls and the gypsum board false ceiling with 2 coats of premium plastic emulsion paint manufactured by M/s. Asian/Berger including primer and touch up Putty as per the requirement etc., complete all as specified and directed	Sft	250		
6	Supply and fixing of 10 mm thk.Writing glass(approx size-4'X3') With white sticker in the back and SS studs for mounting the same etc., complete all as specified and directed	Nos	1		
7	Providing and fixing of 75 mm thk modular prelam partition board, approved colour fabric to match with the existing color scheme etc., complete all as specified and directed	Sft	16		

8	Removal and realignment, repair work of exiting modular workstations including replacement of required damaged spares etc., complete all as specified and directed	Job	1		
	Electrical works				
9	Providing wiring for circuit/sub-main wiring along with earth wire with the following size of FR PVC insulated copper conductor, single core cable of first quality, conforming to relevant IS, Manufactured by M/s Anchor Roma/Finolex/Havells/Crabtree/ABB/Schneider/Polycab and PVC conduit all as specified and directed . Note : Rate quoated for the item deemed to be include for Groove cutting in walls /ceiling and finishing the same with Cement mortar.				
a)	2X2.5 sqmm + 1x 1.5 sqmm earth wire for UPS	Rmt	50.00		
b)	2X2.5 sqmm + 1x 1.5 sqmm earth wire for RAW POWER	Rmt	40.00		
c)	2X4.0 sqmm + 1x 2.50 sqmm earth wire for AC	Rmt	60.00		
10	Supplying and fixing Point wiring for 5/6 Amps modular socket outlet incuding with 5/6Amps modular switch, modular plate, suitable size box along with 2.5sqmmX1.5sqmm FR PVC insulated copper conductor single core cable of first quality, conforming to relevant IS, Manufactured by M/s Anchor Roma/Finolex/Havells/Crabtree/ ABB/Schneider/ Polycab in PVC conduit of required dia concealed in walls etc complete all as specified and directed. Note : Rate quoated for the item deemed to include for the following a) Removing the existing old point and wiring b) Groove cutting in walls /ceiling and making good to walls with Cement mortar.	Nos	4		

11	Supplying and fixing Point wiring for 15/16 Amps modular socket outlet including with 32Amps DP modular switch, modular plate, suitable size box along with 4.00sqmmX2.5sqmm FR PVC insulated copper conductor single core cable of first quality, conforming to relevant IS, Manufactured by M/s Anchor Roma/Finox/Havells/Crabtree/ABB/Schneider/Polycab and PVC conduit concealed in walls etc complete all as specified and directed. Note : Rate quoted for the item deemed to include for the following a) Removing the existing old point and wiring b) Groove cutting in walls /ceiling and making good to walls	Nos	1		
12	Supplying and fixing CAT6 data cable (DIGILINK) for voice & data etc., complete all as specified and directed	Rmt	90		
13	Supplying and fixing RJ45 cable etc., complete all as specified and directed	Nos	4		
14	Supplying and fixing 20Amps metal socket for AC conforming to IS etc., complete all as specified and directed	Nos	1		
TOTAL COST OF A (INTERIOR WORKS) INCLUDING ALL TAXES AND DUTIES				Rs.	
B-FURNITURE-EXECUTIVE CABIN					
1	Supply and fixing of Executive Table(5'6"X2') made out 25mm prelam plyboard with 2mm edge band with powder coated MS base including prelam Modesty panel as per the design.	Nos	1		
2	Supply and fixing of side unit (3'X1'4"X2'6") made out of 19mm prelam plyboard with 2mm edge band including 2 sets of drawer units and openable shutters/doors.	Nos	1		
3	Supply of mobile pedestal (3drawerunit) with casters	Nos	1		
4	Supply and fixing of Meeting Table(5'6"X3') made out 25mm prelam plyboard with 2mm edge band With powder coated MS base as per the design	Nos	1		

5	Supply of high back revolving chair with headrest, chrome casters, adjustable arms and lumber support	Nos	1		
6	Supply of medium back revolving chair with chrome casters, adjustable arms and lumber support	Nos	9		
	TOTAL COST OF B (FURNITURE) INCLUDING ALL TAXES AND DUTIES			Rs.	
	GRAND TOTAL COST OF A+B INCLUDING ALL TAXES AND DUTIES			Rs.	