

BILL OF QUANTITIES**Sub proposed Interior work in BEML RO, Chennai**

Sl.No.	Qty	Unit	Description	Rate	Amount (Rs.)
			Interior Works		
1	68	sft	Providing and fixing full height partition using aluminium frameworks and lined with 12mm board with laminate finish and 3'0" wide glass panel next to door matching to the existing one		
2	1	Nos	Providing and fixing flushdoor with laminate finish fixed using heavy duty hinges,locks,handles and vision panel glass and door closer matching to the existing one.		
3	1	Nos	Providing and fixing table with 25mm top and 18mm side supports with modesty panel and pedestal draw unit as per your requirement. size: 4'0"x2'3"x 2'6"h		
4	36	sft	Providing and fixing full height storage with shutters fixed using auto-close hinges,locks,handles,magneticcatches etc., complete. Size: 5'6"x 6'6"htx1'5"d		
5	2	Nos	supplying of chair		
6	1	set	Charges for dismantling the existing cubical work stations and handing over the same to the client.		
			Electrical Works		
7	1	set	Supply and fixing below fixtures with cabling and light fitting re-location 2 switch 2 sockets - 1 set, Data and voice socket - 1 set and power socket for AC unit 1 No		