

BEML LIMITED, BANGALORE COMPLEX

Tender Number : 6300040011	Period of contract:	Two (02) Months
	EMD : Rs	17310
Sub:Supply of M-Sand,(Plastering Sand), Supply of HDPE empty bags of(30kg Capacity each) filling in bags,stitching,stacking,loading and unloading Sand Bags in train Sets for AW4 Type Tests under 5RS-DM Contract Project of BMRCL test at Kothanur Depot,Bangalore - 560076		

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
1	Supplying of M-sand (Plastering Dry sand) and stacking at a place shown including all lead, lift, transportation, loading and unloading at the place shown etc., complete all as specified and directed by Engineer in charge Note:- The total quantity of M-sand required is 135MT (Dry weight)	Tonne	135		
	GST on Item no(1)		%		
2	Supplying of durable good quality double layer HDPE empty Bags weighing on a weighment scale (each 30 Kgs) and stacking at Kothanur depot as directed by Engineer-in-charge. Note:Sample of HDPE bags to be approved by BEML	Nos	4500		
	GST on Item no(2)		%		
3	Labour Charges for Filling the available dry M-sand in double Side Laminated HDPE bags including stitching the sand bags, weighing on a weighment scale (each 30 Kgs) and stacking inside Kothanur Depot. Etc. as directed by Engineer-in-charge.(Excluding the cost of Sand and HDPE bags) Note:- 1) Required quantity of M-Sand bags is 4500 numbers and each bag weighing 30 kg. 2) The rate is deemed to include for hiring a calibrated weighing scale for measurement and stitching machine for stitching the bags 3) The rate is deemed to include for cost of Nylon thread and labor Cost for stitching the Sand bags after filling 4) The cost is deemed to include for labour Charges for filling the M-sand into HDPE bags. 5) The rate is deemed to include for cost of additional plastic sheet to cover the stacked M-sand bags at the stored location inside Kothanur depot Project to avoid ingress of moisture and loss of material material due to rains when stored.	Nos	4500		
	GST on Item no(3)		%		
4	Labour Charges for Loading and unloading Sand bags into the train set as Specified and directed by Officer incharge 1.The Quoted rate is deemed to include for hiring a tractor/making required transportation arrangement including labor for shifting the Sand bags from stored/stacked location inside depot to the load test area(train set area)for Conducting the test. 2.Contractractor may note that loading and Unloading the Sand bags into train set Would be a onetime activity. 3.Before and After the test cleaning the train set shall be the responsibility of the Contractor 4.Contractractor Should take Proper Care While Loading Sand bags in the Car 5.The Quoted Rate include to Provide the tarpaulin on the floor of train sets to avoid any damages to floor due to moisture Content	Nos	125		
	GST on Item no(4)		%		
5	Supply and fixing heavy duty tarpaulin tripal sheet of Size 21'x15' feet Approx of flayerd 200 GSM Water Proof tarpaulin Sheet (The sheet should be tear resistant & UV resistant) to Cover and Protect the floor,Seats and the train seats etc., complete all as specified and directed by Engineer-in-Charge.	Nos	8		
	GST on Item no(5)		%		
6	Supply and Fixing Tuffpaulin Plastic tarpaulin tripal tadpatri Plastic Sheet of Six Layered of Size approx.15'x9' feet 120 GSM Water Proof Sheet (material should be tear resistant and UV resistant) to Cover M sand to avoid ingress of Moisture and Loss of Material due to rain during Storage at depot etc., complete all as specified and directed by Engineer-in-Charge.	Nos	9		
	GST on Item no(6)		%		
	Total value of work excluding of GST (Rs)				
	TOTAL GST AMOUNT (Rs)				
	Total value of work including of GST (Rs)				

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
-----------	-------------	------	-----	-------------------------------------	-------------

Total Amount in words Rupees_____

Signature of the Contractor With Seal