

Plant Address
BEML Limited,
Mysore - Engine Division
Belvadi Post
Mysore-570018
Karnataka, India

REQUEST FOR QUOTATION

DATE: 13.02.2021
VENDOR CODE: 694320
CLOSING DT: 17.03.2021
TIN NO: 29040051691

TEL:0821-2402422,
FAX:0821-2402442,0821-2402429,0821-2402434,
EMAIL:bemlz@bsnl.in,bemlmysz@sancharnet.in,beml
mys@sancharnet.in,
Our Ref :MZ01/ ZMN/1060018772

Dear Sirs,
Please let us have your lowest non negotiable quotation on F.O.R. Destination basis, in duplicate, for supply of following items before 2.00 pm on the Closing Date indicated as above, *addressed to the Senior Manager-Purchase, of the Plant Address mentioned in this Request for Quotation.*

SL.No.	Our Part Number / Vendor Part Number Description	QTY REQD	PROC. UNIT						
00001	<p>SITC OF PVC STRIP CURTAINS - MATERIAL</p> <p>Supply, Installation, Testing, Commissioning and Prove out of PVC Strip Curtains - Clear - 200mm x 3mm double Ribbed - with 50% overlap for existing door openings of size:</p> <p>1)Bay1 - 16.6ft w x 16ft h</p> <p>2)Bay3 - 16.6ft w x 16ft h</p> <p>3)Bay4 - 16.6ft w x 16ft h</p> <p>4)Bay5 - 16.6ft w x 16ft h</p> <p>5)Bay6 - 16.6ft w x 16ft h</p> <p>6)Shoot Peening m/c side opening 16.7ft w x 12.6 ft h</p> <p>7)PDB3 side opening 11.3ft w x 15.6ft h</p> <p>8)Maintenance Room side opening 4ft w x 6.6ft h</p> <p>9)Holding store side opening - 15ft w x 13.3ft h</p> <p>10)VIP Entry Door 10ft w X 19.5ft h</p> <p>Total Area - 3,210 sq. ft</p> <p>Firm to supply required size PVC Strip Curtains - Clear - 200mm x 3mm Double Ribbed size, along with Material Test and Guarantee Certificate. (Product Catalogue / Data sheet to be provided)</p> <table><tr><td>Qty.</td><td>unit</td><td>Deliv.date</td></tr><tr><td>1.000</td><td>Activ.unit</td><td>31.03.2021</td></tr></table> <p>The item covers the following services:</p>	Qty.	unit	Deliv.date	1.000	Activ.unit	31.03.2021	1.000	Activ.unit
Qty.	unit	Deliv.date							
1.000	Activ.unit	31.03.2021							
01	Supply of PVC Strip Curtains with Access	3,210	FT2						

SL.No.	Our Part Number / Vendor Part Number Description	QTY REQD	PROC. UNIT
00002	<p>SITC OF PVC STRIP CURTAINS - LABOUR</p> <p>Firm's Scope of work (Labor Portion) : Supply Installation Testing Commissioning and Prove out the PVC Strip Curtains to existing doors/openings. Firm to quote for total 3,210 sq. ft Area.</p> <p>Guarantee: One year from the Date of Supply against all manufacturing defects and workmanship for fixing /installation.</p> <p>Note: Firm to visit our works and get the required details like door/opening sizes before submitting their Quotation.</p> <p>Qty. unit Deliv.date 1.000 Activ.unit 31.03.2021</p> <p>The item covers the following services:</p>	1.000	Activ.unit
01	Installation, Testing, Commissioning	3,210	FT2
00003	<p>OPTIONAL-SITC CURTAIN SLIDING ARRANGMNT.</p> <p>OPTIONAL -- Supply, Installation, Testing, Commissioning and Prove out of Strip Curtain Sliding Arrangement - for easy movement of Forklift/Lorry etc. without damaging the PVC strips and to facilitate easy VIP movement. Firm to Quote the Rate in Running Ft. including complete material and labor portion. (The total width of all 10 door openings is about 140ft).</p> <p>BEML will decide whether to opt for sliding type OR Fixed type and will select for which door openings it is required sliding/fixed type.</p> <p>Qty. unit Deliv.date 1.000 Activ.unit 31.03.2021</p> <p>The item covers the following services:</p>	1.000	Activ.unit
01	Optional - Curtain Sliding Arrangement	150	FT

Thanking you
Yours faithfully
For BEML Limited.,

Authorized Signatory

Refer Annexure for TERMS and CONDITIONS