

BEML LIMITED, BANGALORE COMPLEX

RMM/6300027974/2019

Date: 07.06.2019

ISSUED TO:	Period of contract:	45 Days
	EMD :	3500.00

SCHEDULE 'A' - BILL OF QUANTITIES

Sub: Proposed panel painting facility at the basement of N-1 hangar in BEML Limited, Bangalore Complex, Bangalore-560075

Sl. No	Description	Unit	Qty	Rate/unit in figures & in words Rs.	Amount(Rs)
1	Surface excavation not exceeding 30cm deep and averaging 15cm deep and getting out including levelling, neatly dressing etc., completed all as specified & directed by Engineer-in-charge.	Sqm	120		
2	Providing and laying in Position Plain cement concrete 150mm thick in mix proportion 1:2:4 using 20mm down graded granite aggregate for hard standing, laid in layers, well compacted, finishing the surface even & smooth including curing, tools & tackles etc., complete all as specified and directed by Engineer in charge.	Sqm	120		
3	Fabricating, hoisting, erecting & fixing in position MS structural steel frame /truss work using available MS channels, angles, plates, flats etc., including cutting, welding, bending to required shape, bolting, cleaning the rust scales to the satisfaction of the Engineer in charge and applying a coat of red oxide primer levelling and erection at all elevations, levels & heights etc., complete all as specified and directed by the Engineer in charge	Kgs	800		
	Note: (a) The required quantity of MS structural steel like MS channels, angles, plates, flats etc., will be supplied by BEML				
	(b) The rate quoted by the Contractor is deemed to include for labour & consumables such as welding machine, welding rods, gas etc. for the work				
	(c) The rate quoted by the Contractor is deemed to include for providing and removal of scaffolding / staging wherever necessary as per site conditions				
	(d) The quoted rate of the contractor is deemed to include for segregating, lifting, shifting the available scrap material from the location shown by BEML to the work site. Vehicle for shifting the material will be provided by BEML				
4	Fixing of available 0.63mm or available thickness corrugated mild steel sheeting fixed with L-type or J-Type or cranked hook bolts with waterproof bitumen washers etc., complete all as specified and directed by the Engineer-in-charge Note: The required quantity of roof sheet/corrugated sheet will be supplied by BEML	Sqm	120		
5	Carting away unwanted and unusable excavated soil outside the site premises to a distance not exceeding 1.50KM and dumping at a place shown inside factory including all lead and lift etc., complete all as specified and as directed by Engineer in charge.	Cum	6		
	Total Amount excluding GST			Rs.	
	GST Amount			Rs.	
	Total Amount inclusive of GST			Rs.	
TOTAL AMOUNT IN WORDS: RUPEES					

Signature of the Contractor
With seal