

	TECHNICAL DELIVERY CONDITION	Project: MRS1
Aggregate	Floor coving assembly, Kick plate & Wire nets.	DOC No.: GR/TD/4961
BEML Enquiry/ RFQ Reference :		

Sl. No.	Technical Delivery Conditions	COMPLIED	NOT COMPLIED
1	Each of the Floor coving assembly, Kick plate & wire nets shall confirm to the tender drawing requirements.	<input type="checkbox"/>	<input type="checkbox"/>
2	The material used shall be austenitic stainless steel to grade SUS 304 / AISI 304, 2B finish and shall be procured from reputed sources like M/s. SAIL or M/s. JSL Stainless Pvt. Ltd.	<input type="checkbox"/>	<input type="checkbox"/>
3	The firm shall submit material test certificate for chemical composition and mechanical properties from the source.	<input type="checkbox"/>	<input type="checkbox"/>
4	Due care shall be taken to ensure quality of welding and after fabrication the weld areas shall be pickled and passivated. Pickling & Passivation process details shall be submitted along with the technical bid.	<input type="checkbox"/>	<input type="checkbox"/>
5	Fabrication of the assembly shall be carried out by qualified welders. Welder qualification certificate and Welding Process Qualification (WPS & PQR) as per EN / ISO / DIN standard shall be submitted along with the technical bid.	<input type="checkbox"/>	<input type="checkbox"/>
6	The Floor coving assembly, Kick plate & wire nets assemblies shall be fabricated using dedicated jigs & fixtures.	<input type="checkbox"/>	<input type="checkbox"/>
7	The Floor coving assembly, Kick plate & wire nets shall be manufactured using dedicated CNC tooling and the part shall be free of die marks & scratches .	<input type="checkbox"/>	<input type="checkbox"/>
8	The supplier shall submit detailed manufacturing process for each of the Floor coving assembly, Kick plate & wire nets along with the technical bid.	<input type="checkbox"/>	<input type="checkbox"/>
9	The Floor coving assembly, Kick plate & wire nets shall be supplied without bead blasting.	<input type="checkbox"/>	<input type="checkbox"/>
10	After fabrication, the finish products shall be of sound quality without any defects.	<input type="checkbox"/>	<input type="checkbox"/>
11	100% quantity of the Floor coving assembly, Kick plate & wire nets shall be subjected to visual and dimensional inspection. Inspection reports shall be submitted along with supplies.	<input type="checkbox"/>	<input type="checkbox"/>
12	Packing shall be done individually and due care shall be taken during packing and ensure damage free product. The damages during transit will be supplier's responsibility.	<input type="checkbox"/>	<input type="checkbox"/>
13	The supplier shall obtain sample approval and fitment trials for Floor coving assembly, Kick plate & wire nets from BEML before taking up mass production.	<input type="checkbox"/>	<input type="checkbox"/>
14	Part number shall be marked on all Floor coving assembly, Kick plate & wire nets using permanent marker. However, use of label for mentioning the part number is not acceptable.	<input type="checkbox"/>	<input type="checkbox"/>

Signature of the Bidder with Seal
(Name, Designation & Address)