

ISSUED TO:	Period of contract:	03 Months
	EMD :	Rs. 14,980/-
Sub: -Proposed repairs to the compound wall in the Northern side (along Malleshpalya main road) of BEML Township, Bangalore.		

SCHEDULE 'A' BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/ unit in fig. & in words (Rs)	Amount (Rs)
1	surface excavation to remove rank vegetation bushes not exceeding 30 cm deep and above 15 cms average depth all along the compound wall and getting out etc., complete all as specified and directed by Engineer-in-charge.	Sqm	200		
2	Felling down the trees exceeding 30cm but not exceeding 100cm girth including cutting of trunk and branches and stacking of serviceable material and disposal of unserviceable material to a distance not exceeding 50 m and clearing site etc., complete all as specified and directed by Engineer-in-charge.	No.	9		
3	Dismantling the existing Size stone masonry wall in any thickness and in any position, stacking of good quality size stones for re-use and disposal of unserviceable material from the premises etc., complete all as specified and directed by Engineer-in-charge. Note: The dismantled materials/debris should be removed immediately from the premises without disturbing the regular public / traffic movement on the road and the quoted rate is deemed to include for all lead & lift etc.	Cum	60		
4	Demolition/dismantling the existing cement concrete / coping concrete on top of wall in any description and in any position etc., complete all as specified and directed by Engineer-in-charge. Note: The dismantled materials should be removed immediately from the premises without disturbing the regular public / traffic movement on the road and the quoted rate is deemed to include for all lead & lift etc.	Cum	7		
5	Constructing size stone masonry superstructure wall built in Cement Mortar 1:6 using available size stones, well bonded, bedded and solidly hearted in courses not less than 20cms high and brought upto courses including curing etc., complete all as specified and directed by Engineer-in-charge.	Cum	42		
6	Providing and constructing size stone masonry superstructure wall built in Cement Mortar 1:6, well bonded, bedded and solidly hearted in courses not less than 20cms high using good quality granite size stones including chisel/hammer dressing to face stones & corner stones of pillars including curing etc., complete all as specified and directed by Engineer-in-charge.	Cum	54		
7	Providing struck pointing in cement mortar 1:4 to the size stone masonry superstructure wall including curing, tools & tackles, scaffolding as required at site etc., complete all as specified and directed by Engineer-in-charge.	Sqm	1900		

Sl. No	Description	Unit	Qty	Rate/ unit in fig. & in words (Rs)	Amount (Rs)
8	Providing and laying in position plain cement concrete of Mix proportion 1:2:4 of min. 75mm thickness for coping/similar works using 20mm down graded granite aggregate, well compacted & top surface finished smooth & even using extra cement mortar including grouting MS Y angles, centering, shuttering as per site requirement etc complete all as specified and directed by Engineer-in-charge.	Cum	7		
9	Rendering/Plastering 15mm thick in Cement Mortar 1:4 on stone/brick masonry or concrete surfaces of compound wall including finishing the surface smooth & even including curing, scaffolding as required at site etc., complete all as specified and directed by Engineer-in-charge.	Sqm	50		
10	Erecting & fixing in position the existing MS grill, providing necessary repair/ fabrication work to the grill wherever damaged, cleaning the rust and scales to the satisfaction of Engineer-in-charge. etc.,complete all as specified and directed by Engineer in charge. Note: a) The MS grill will be supplied by BEML. (b) The quoted rate is deemed to include for labour, welding machines, gas, welding rods etc required for the repair/fabrication if any required.	Kgs	300		
11	Preparing the existing steel surfaces & applying two coats of synthetic enamel paint of first quality, approved colour manufactured by M/s. Asian Paints/Berger including lead, lift, materials, labour, tools & tackles, etc.,complete all as specified and as directed by Engineer in charge.	Sqm	10		
12	Carting away unwanted and unusable excavated soil,debris outside the site premises to a distance not exceeding 1.50KM including all lead and lift, transportation etc., complete all as specified and as directed by Engineer in charge.	Cum	55		
NOTE: THE RATE QUOTED FOR ALL THE ABOVE ITEMS IS DEEMED TO INCLUDE FOR PROVIDING AND REMOVAL OF SCAFFOLDING/STAGING AS REQUIRED AT SITE					
	Total Value of work excluding GST/Taxes (Rs)			Rs.	
	GST/Taxes			Rs.	
	Total Value of work inclusive of GST			Rs.	

(Total Amount in words Rupees.....)

Signature of the Contractor  
with seal