

ISSUED TO:	Period of contract:	One Month
	EMD :	Rs. 25,564/-

Sub:Supply of M-Sand, Supply of HDPE empty bags of (30 kg capacity each) filling in bags , stitching, stacking, loading and unloading sand bags in train sets for 3RS-DM Project of BMRCL for type test at Peenya Depot, Bangalore.

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
1	Supply of M-Sand(Plastering Dry sand) and stacking at a place shown including all lead, lift, transportation, loading and unloading at a place as shown at Peenya Depot of BMRCL Project etc., complete all as specified and directed by Engineer in charge. Note : a) Total quantity of M-Sand required is 172 MT (Dry weight). b) Before supply, sample of M-sand should be approved by BEML.	Tonne	172		
	GST on Item no(1)		%		
2	Supply of durable good quality HDPE empty bags Virigin Grade, Double side laminated of 30kg capacity and stacking at Peenya Depot, Bangalore. Note: Sample of HDPE bags to be approved by BEML.	Nos	9100		
	GST on Item no(2)		%		
3	Labour charges for filling the available dry M-sand in double side laminated HDPE bags including stitching the sand bags, weighing on a weighment scale (each bag has 30kg capacity) and stacking inside Peenya depot of BMRCL Project etc., as directed by Engineer-in-charge. (Excluding the cost of sand and HDPE bags) Note: - 1) Required quantity of M-Sand bags is 9100 numbers and each bag weighing 30 kg after filling. 2) The rate is deemed to include for hiring a calibrated weighing scale for weighment and stitching machine for stitching the bags. 3) The rate is deemed to include for cost of Nylon thread and labor cost for stitching the sand bags after filling. 4) The cost is deemed to include for labor charges for filling the M-sand into HDPE bags. 5) The rate is deemed to include for cost of additional plastic sheet to cover the stacked M-sand bags at the stored location inside Peenya depot of BMRCL Project to avoid ingress of moisture and loss of material due to rains when stored.	Nos	9100		
4	Labor charges for loading and unloading sand bags into the train set as specified and directed by the officer-in-charge. Note: 1. The quoted rate is deemed to include for hiring a tractor/making required transportation arrangement including labor for shifting the sand bags from stored/stacked location inside depot to the load test area (train set area) for conducting the test. 2. Contractor may note that loading and unloading the sand bags into train set would be a onetime activity. 3. Before and after the test cleaning the train set shall be the responsibility of the contractor. 4. Contractor should take proper care while loading sand bags in the car. 5. The quoted rate include to provide the tarpaulin on the floor of train sets to avoid any damage to floor due to moisture content.	Nos	9100		

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
5	<p>Labor charges for loading and unloading sand bags into the train set as specified and directed by the officer-in-charge.</p> <p>Note: 1. The above service is optional & will operate if required by BEML.</p> <p>2. The quoted rate is deemed to include for hiring a tractor/making required transportation arrangement including labor for shifting the sand bags from stored/stacked location inside depot to the load test area (train set area) for conducting the test.</p> <p>3. Contractor may note that loading and unloading the sand bags into train set would be a onetime activity.</p> <p>4. Before and after the test cleaning the train set shall be the responsibility of the contractor.</p> <p>5. Contractor should take proper care while loading sand bags in the car.</p> <p>6. The quoted rate include to provide the tarpaulin on the floor of train sets to avoid any damage to floor due to moisture content.</p>	Nos	4534		
	GST on Labor		%		
	Total value of work excluding GST			Rs.	
	TOTAL GST AMOUNT			Rs.	
	Total value of work inclusive of GST			Rs.	

Total Amount in words Rupees_____

Signature of the Contractor
with seal